

To All Bidders:

The following additions, deletions and modifications to the Bidding Documents for the Subject Project as originally issued, October 12<sup>th</sup>, 2019, are hereby incorporated into said documents and shall be fully considered in preparation of proposals:

**SPECIFICATIONS - ARCHITECTURAL**

SA-1 TABLE OF CONTENTS, page i:

**DELETE** DIVISION 4 – MASONRY, Section 04 05 00 Masonry Mortar and Grout, and Section 04 22 00 Concrete Unit Masonry from the table of contents.

SA-2 Section 00 11 16, Paragraph 1.4:

**ADD** a copy of the Pre-Bid Walkthrough Sign-In Sheet for informational purposes.

SA-2 Section 08 70 00 FINISH HARDWARE, Paragraph 2.8:

**ADD** To HW-1a: "Provide Wall Stop 230W at Door WCO-MX1a in lieu of Floor Stop."

**ADD** To HW-1b: "Provide Wall Stop 230W at Door WCO-MX1b in lieu of Floor Stop."

**DRAWINGS – ARCHITECTURAL**

DA-1 Drawing A0.1v, Drawing A0.1h, and Drawing A0.1e; Contact Information:

**CHANGE** the phone number of the Project Manager to (509) 663-0555.

DA-2 Drawing A2.3v, Door Schedule:

**CHANGE** Door WHS-115c Opening Size to 3'-0 x +/-6'-10, field verify w/ existing opening and new frame installation.

DA-3 Drawing FH2.1v, Enlarged Floor Plan:

**ADD** "Exit Sign by District, Provide J-Box in structural steel beam and assist the District in routing 120v power through the beam into the ceiling space of Room FH101."

DA-4 Drawing FH2.1v, Enlarged Floor Plan:

**ADD** "Exit Sign by District, Provide J-Box in structural steel beam and assist the District in routing 120v power through the beam into the ceiling space of Room OR201."

DA-5 Drawing PI2.1v, Enlarged Floor Plan:

**ADD** "Exit Sign by District, Provide J-Box in structural steel beam and assist the District in routing 120v power through the beam, into the ceiling space of Room PI221 or to the exposed outlets and conduit on the north concrete column as may be selected by the District."

DA-6 Drawing HS6.1v, Enlarged Reflected Ceiling Plan:

**ADD** the note "by District" to the existing note "New Exit Sign".

DA-7 Drawing A2.2h, Door Schedule:

**CHANGE** Door WHS-48a Opening Size to +/-7'-0' x +/-7'-0, field verify w/ existing opening and new frame installation.

DA-8 Drawing FH2.1h, Enlarged Floor Plan:

**CLARIFY** wiring shall be concealed in wiring in mullions and non-masonry columns, assist District in concealing 120v power to door operator in the mullion.

DA-9 Drawing OR2.1h, Enlarged Floor Plan:

**CLARIFY** wiring shall be concealed in wiring in mullions and non-concrete columns, assist District in concealing 120v power to door operator in the mullion.

DA-10 Drawing PI2.1h, Enlarged Floor Plan:

**CLARIFY** wiring shall be concealed in wiring in mullions and non-concrete columns, assist District in concealing 120v power to door operator in the mullion.

## **WENATCHEE SCHOOL DISTRICT**

By: Paul Coppock, The DOH Associates, PS

Attachments: Pre-Bid Walkthrough Sign-In Sheet.



January 3, 2020

Project #1904  
WENATCHEE SCHOOLS  
SECURITY IMPROVEMENTS  
Wenatchee School District

## **BIDDER LIST**

### **PRIME BIDDERS**

#### Halme Builders

27241 WA-2

Davenport, WA 99122

Phone: (509) 725-1200

Fax: (509) 725-8600

Email: [dan@halmebuilders.com](mailto:dan@halmebuilders.com)

#### Norris Construction, LLC

6584 Beam Street

West Linn, OR 97068

Phone: (503) 723-3393

Email: [norrisconstruction@gmail.com](mailto:norrisconstruction@gmail.com)

#### Western States Construction, Inc.

P.O. Box 208

Valleyford, WA 99036

Phone: (509) 888-0600

Email: [wsc@air-pipe.com](mailto:wsc@air-pipe.com)